ETS CORP. T & M PROPOSAL

Date:	October 28, 2026
Quote No.:	**348-26 REV II (T&M)**
Contact:	Eng. Jorge Sánchez
Contractor:	Amgen
Proposal Type:	Time & Material Page 1 of 3

Project/Area: **AMGEN - AML1 ROOM 4137 PACKING AREA AND CORRIDOR 547 (RE-FLAKE - PATCH REPAIR)**	Location: **Juncos, Puerto Rico**

We are pleased to present our Time & Material (T&M) proposal for the reference project.

TO BE PERFORMED:

Re-Flake on the reference project, which consists of the following:

SCOPE OF WORK:

- Surface preparation with diamond grinder
- Installation of:
  - Sikafloor 264 (Color Light Gray) Base Coat + Sikafloor Flake (Color Salt & Pepper)
  - Sikafloor 217 Grout Coat
  - Sikafloor 217 2nd Grout Coat
  - Sikafloor 217 Topcoat
  - Sikafloor 315 2nd Topcoat

1. ESTIMATED LABOR

POSITION	QTY	EST. HOURS	RATE / HR	AMOUNT
Project Manager	1	5	$90.00	$450.00
Supervisor	1	24	$60.00	$1,440.00
Labor	4	68	$40.00	$2,720.00
Total Estimated Labor	**6**	**97**		**$4,610.00**

2. ESTIMATED WORK SCHEDULE

Project duration: approximately 5 working days (one coat per day due to curing time between coats). Hours shown as Supervisor / Labor.

DAY	ACTIVITY	CREW	HOURS
Day 1	Mobilization, area protection, diamond grinding, Sikafloor 264 base coat + Sikafloor Flake broadcast	Supervisor + 4 Labor	8 / 32
Day 2	Remove excess flake, sand/vacuum, Sikafloor 217 grout coat	Supervisor + 4 Labor	4 / 12
Day 3	Sikafloor 217 2nd grout coat	Supervisor + 2 Labor	4 / 8
Day 4	Sikafloor 217 topcoat	Supervisor + 2 Labor	4 / 8
Day 5	Sikafloor 315 2nd topcoat, cleanup, demobilization	Supervisor + 2 Labor	4 / 8
Day 1–5	Project coordination, client meetings, inspection and closeout	Project Manager	5 (PM)

Date:	October 28, 2026
Quote No.:	**348-26 REV II (T&M)**
Contact:	Eng. Jorge Sánchez
Contractor:	Amgen
Proposal Type:	Time & Material Page 2 of 3

3. ESTIMATED MATERIALS & EQUIPMENT

DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
Sikafloor 264 (Light Gray) – Base Coat	2	Kit	$550.00	$1,100.00
Sikafloor 217 – Grout Coats & Topcoat	5	Kit	$420.00	$2,100.00
Sikafloor 315 – 2nd Topcoat	2	Kit	$610.00	$1,220.00
Sikafloor Flakes (Salt & Pepper)	4	Box	$245.00	$980.00
Roller Covers 9"	8	Ea	$18.00	$144.00
Roller Covers 4"	12	Ea	$9.00	$108.00
Squeegees	3	Ea	$65.00	$195.00
Brushes	10	Ea	$7.80	$78.00
Mixing Drill	1	Ea	$595.00	$595.00
Mixer	1	Ea	$395.00	$395.00
Total Estimated Materials & Equipment				**$6,915.00**

4. ALLOCATION BY AREA

AREA	QTY/UNIT	MATERIAL	LABOR	TOTAL
Room 4137 Packing Area (Patch Repair)	210 sf	$4,079.00	$2,719.00	$6,798.00
Corridor 547 Area (Patch Repair)	45 sf / 2 lf	$2,836.00	$1,891.00	$4,727.00
Total		**$6,915.00**	**$4,610.00**	**$11,525.00**

5. ESTIMATED T&M SUMMARY

Estimated Labor	$4,610.00
Estimated Materials & Equipment	$6,915.00
Subtotal	**$11,525.00**
B2B 4% (on labor)	**$184.40**
ESTIMATED TOTAL	**$11,709.40**

Date:	October 28, 2026
Quote No.:	**348-26 REV II (T&M)**
Contact:	Eng. Jorge Sánchez
Contractor:	Amgen
Proposal Type:	Time & Material Page 3 of 3

Terms & Conditions

- Payment Terms: Net 30 days.
- **Quotation valid for 15 days.**
- ***Upon approval of the proposal, all costs shall be separated into labor and materials in the Work Order or Purchase Order and must be in the name of ETS Corp.***
- **NEW CUSTOMERS ARE REQUIRED TO SUBMIT A DEPOSIT OF 50% OF THE REFERENCE QUOTE.**
- Cost is based on regular hours (8 hours daily, Monday to Friday) Overtime not included.
- Prices may fluctuate due to variation in raw material and freight cost in the market.
- If approved, please send purchase order to purchaseorder@etspr.com or estimados@etspr.com .
- Purchase orders must reference the corresponding quote.
- Customer will provide water source & electrical power, including 120, 240 & 480V 3 phase.
- Client is responsible for maintaining all areas free of heavy equipment in order to proceed as scheduled.
- Once installation has begun, there should not be interruption as this may cause system contamination.
- Price based on one mobilization, areas must be ready and available to start working as planned. Additional mobilization cost will range between $2,000.00 and $2,500.00 each.
- Time delays in area clearance procedure or any other situation under the customer's responsibility and control which cause lost in time of ETS personnel, will be charged separately.
- Additional requirements not specified in this proposal will be quoted separately. Changes in floor slope or any patching area not considered in prices. The installation shall follow existing floor levels and application of system is not intended to correct drainage problems.
- Changes in scope, square feet, thickness or material will not be performed without written consent from client.
- One-year warranty after the date of installation.
- Additional requirements not specified in this proposal will be quoted separately.
- A certain number of hours are required for product to cure, before continuing with the installation process.
- Vapor barrier not included.

Important Note: Quote is to be considered for all areas for the established price. If all areas are not to be considered, pricing to given quote could change. This quote is based on it being a continuous job, without interruptions.

Acknowledge by:

Carlos A. Soto
Senior Project Manager